

University of Nebraska - Lincoln

**DigitalCommons@University of Nebraska - Lincoln**

---

Historical Materials from University of Nebraska-  
Lincoln Extension

Extension

---

1970

## EC70-793 Agricultural Engineers' Digest : Tilt-Up Concrete Horizontal Silo Construction

Follow this and additional works at: <http://digitalcommons.unl.edu/extensionhist>

---

"EC70-793 Agricultural Engineers' Digest : Tilt-Up Concrete Horizontal Silo Construction" (1970). *Historical Materials from University of Nebraska-Lincoln Extension*. 4014.

<http://digitalcommons.unl.edu/extensionhist/4014>

This Article is brought to you for free and open access by the Extension at DigitalCommons@University of Nebraska - Lincoln. It has been accepted for inclusion in Historical Materials from University of Nebraska-Lincoln Extension by an authorized administrator of DigitalCommons@University of Nebraska - Lincoln.

# AD

RECEIVED  
OCT 18 1972  
COLLEGE OF AGRICULTURE

## Tilt-Up Concrete Horizontal Silo Construction MWPS-15

### AGRICULTURAL ENGINEERS' DIGEST


#### Introduction

Walls of tilt-up concrete can be built with a minimum of forming because all vertical slabs are cast flat, then erected.


Concrete mix need not be elevated, but equipment is required for raising the cast and cured panels.

Below ground silos have several advantages over above ground silos:

- Excavation soil can be used to:  
Build or repair feedlots or earth resting mounds.  
Reduce depth of cut.



- Soil provides support for walls.
- Silage need not be elevated during filling.
- After partial filling, closed end can provide access ramp in smaller silos.
- Relatively constant cool soil temperatures aid in maintaining silage quality.



**NOTE:** A long paved ramp at the closed end is not recommended because long "floor" and side-walls are relatively expensive and greatly reduce capacity. Spoilage may be high in smaller areas.

Above ground silos also have advantages:

- Less site preparation.
- Adaptable to flat or poorly-drained areas.
- The buttresses shown can support 2 walls to form the center partitions between 2 silos.

#### Site

- Locate the silo for convenient access during filling, packing, and unloading. High ground is preferred.
- Odors may be a nuisance if a large silo is too close to a residence.
- Divert ground water away from the site.
- Provide drainage away from the lower end of the floor that will not pollute a well or spring.
- Provide protection from blowing snow.
- Do site grading and excavating before starting construction. Provide access for panel lifting equipment (tractor or truck) along both walls outside the silo.
- Do not select a site where part of the silo is above ground and part below ground: panel design is inadequate for part-soil, part-buttress support.

#### Specifications

**Concrete:** strong, dense, and resistant to silage acids.

**Cement:** at least 7 sacks per cubic yard of concrete.

**Water:** no more than 5 gallons of water per sack of cement, including water in the aggregates.

**Air Entraining:**

Maximum Aggregate Size	Amount of Air
3/4"	7%
1/2"	8%
3/8" or less	9%

**Forms:** rigid and well braced. Oil forms before placing concrete.

**Placing:** 5 to 15 seconds vibration, or spading, next to the forms to prevent honeycombs.

**Curing:** concrete does not dry; the paste sets by a chemical reaction between cement and water.

Cure panels and buttresses before tilting: 5 to 7 days with air temperatures between 50° and 100°F; 10 days if temperature is 40°-50°F.



Wet surface of concrete, and keep covered with polyethylene sheet. In cold weather cover the plastic with 24" of straw to prevent freezing.

**Silo Floor:** a concrete floor is required in both above and below ground silos for structural stability.

A uniform slope of 1" per 8' of length is desirable.

Cast floor in lengthwise strips 10'-12' wide. (note bars along edge of slab in above-ground silos—no other reinforcing is required in floor).



Cast a uniform thickness of 5". Thicken edge at an open end to 8".

### Wall Slope

Do not change the design wall slope.

The below ground silos are designed for 1/3 wall slope; steeper slopes will be subjected to greater soil pressures and will require more steel.

The above ground silos are designed for about 1/4 slope; flatter slopes will be subjected to greater silage pressure, and steeper slopes may result in buttresses too narrow to prevent overturn.



**Table 1. Capacities of silos per 10 feet of length**  
(Level full at 50 cu ft = 1 ton)

	Silo Floor Width									Closed End Ratio
Depth	20	30	40	50	60	70	80	90	100	
10 bu tons	1800 45	2600 65	3400 85	4200 105	5000 125	5800 145	6600 165	7400 185	8200 205	1/8
12 bu tons	2208 55	3168 79	4128 103	5088 127	6048 151	7008 175	7968 199	8928 223	9888 247	1/7
14 bu tons	2632 66	3752 94	4872 122	5992 150	7112 178	8232 206	9352 234	10472 262	11592 290	1/6
16 bu tons	3064 77	4344 109	5624 141	6904 173	8184 205	9464 237	10744 269	12024 301	13304 333	1/5
18 bu tons	3528 88	4968 124	6408 160	7848 196	9288 232	10728 268	12168 304	13608 340	14048 376	1/5
20 bu tons	4000 100	5600 140	7200 180	8800 220	10400 260	12000 300	13600 340	15200 380	16800 420	1/4

**Example:** 50' wide, 12' deep, 120' long, 1 end closed.

Capacity per 10', from table = 127 tons

Capacity per 120' = 12 x 127 = 1524 tons  
Closed end holds additional silage.

Multiply closed end ratio for silage depth times the capacity /10':

$1/7 \times 127 = 18$  (about)

Open end will be less than full. Deduct for capacity lost:

Slope of Silage	Deduction
1/4	closed end capacity
1/2	2 x " " "
1/1	4 x " " "

Assume slope of 1/2

closed end capacity = 18 tons

deduct 2 x 18 = 36 tons


Total capacity = 1544 + 18 - 36 = 1526 tons.



## BELOW GROUND SILOS


### Construction Steps

1. Excavate, grade, and uniformly compact dampened sub-grade. Excavate for 5½"x12" footings.
2. Cast footings.
3. Form and cast floor (no reinforcing is required).
4. Build wall panel forms of 2x6 lumber over polyethylene film along edges of floor.
5. Place vertical reinforcing on 1" chairs.



CHAIR DETAIL

6. Place horizontal bars; wire enough intersections to hold them in place.
7. Locate and place lifting and tie-back inserts with top of insert flush with top of forms. Oil inside of threads. To prevent concrete from filling threads, place oiled threaded dummy bolts or polystyrene plugs into inserts flush with top of forms.



INSERT AND PLUG

8. Tie anchor reinforcing, R, in place.
9. Place, vibrate, and cure concrete.
10. Set aligning posts in bank—these hold the panels at the correct angle during setting of tie-backs and backfilling.

11. Place concrete in post holes for tie-back anchor reinforcement, A, or set screw anchors.
12. Lay drain tile along outside of footings.
13. Lift slabs into place. Anchor to tie-back bar, A, or screw anchor.
14. Cast concrete in trench over bar A.
15. Seal joints at floor and between panels with mortar.
16. Backfill.


### Endwalls

There are several ways of constructing an end-wall. One is shown below.

1. Extend footings for sidewalls beyond end of floor the distance shown below:

Silo Depth:	10'	12'	14'	16'	18'	20'
Footing Extension:	3'-4"	4'-0"	4'-8"	5'-4"	6'-0"	6'-8"

2. Erect typical sidewall panels.
3. Cast 2 corner endwall panels wider at the top than at the bottom. The difference will be the same as the footing extension, above. Note that total width of the bottoms of the endwall panels must equal the silo floor width.
4. Endwall panels are raised and secured the same as the sidewall panels.




ENDWALL DETAIL—Example


**Example:** silo 18' deep, 36' wide, 12' panel width. Footing extension is 6'. Two Full Panels, 12'x18', are needed. Two Tapered Corner Panels, 6' at the bottom, and 6'+6', or 12', wide at the top.




**BELOW GROUND SILOS**  
**Panels 8' Wide, 10' to 20' High**  
**One Tie-Back Per Panel**



**PANEL REINFORCING**



**INSERT REINFORCING DETAIL**






**SECTION**

**Table 2. Panel dimension and reinforcement schedule (8' wide panels—one tie-back each)**

Panel Height	Insert Location $I_v$	Vertical Reinforcement	Anchor Insert Reinf R	Horizontal Reinforcement	Tie-Back		
					Wt/Lb	Static Tension, Lb	Bar Size
10'-0"	2'-6"	6 #4 @ 18"	2 #4	7 #4 @ 18"	5,500	2,140	#4
12'-0"	3'-0"	6 #4 @ 16"	2 #5	8 #4 @ 18"	6,600	3,070	#4
14'-0"	3'-6"	8 #4 @ 12"	2 #5	9 #4 @ 18"	7,700	4,180	#4
16'-0"	4'-0"	13 #4 @ 7½"	3 #5	11 #4 @ 18"	8,800	5,460	#6
18'-0"	4'-6"	19 #4 @ 5"	3 #5	12 #4 @ 18"	9,900	6,920	#6
20'-0"	5'-0"	16 #5 @ 6"	4 #5	13 #4 @ 18"	10,400	8,500	#6



**BELOW GROUND**  
**Panels 12' Or 16' Wide, 10' To 20' High**  
**Two Tie-Backs Per Panel**



**INSERT REINFORCING DETAIL**


**PANEL REINFORCING**

**Table 3. Panel dimension and reinforcement schedule (12' & 16' wide panels, 2 tie-backs each)**


Panel Width	Panel Height	Insert Location		Vertical Reinforcement	Insert Reinf R	Horizontal Reinforcement	Tie-Back		
		$l_V$	$l_H$				Wt/Lb	Static Tension, Lb	Bar Size
12'-0"	10'-0"	2'-6"	2'-8"	8 #4 @ 18"	2 #4	7 #4 @ 18"	8,250	1,600	#4
12'-0"	12'-0"	3'-0"	2'-8"	9 #4 @ 16"	2 #4	8 #4 @ 18"	9,900	2,300	#4
12'-0"	14'-0"	3'-6"	2'-8"	12 #4 @ 12"	2 #4	9 #4 @ 18"	11,550	3,130	#4
12'-0"	16'-0"	4'-0"	2'-8"	19 #4 @ 7½"	2 #4	11 #4 @ 18"	13,200	4,100	#4
12'-0"	18'-0"	4'-6"	2'-8"	28 #4 @ 5"	2 #5	12 #4 @ 18"	14,850	5,190	#6
12'-0"	20'-0"	5'-0"	2'-8"	24 #5 @ 6"	2 #5	13 #4 @ 18"	15,600	6,380	#6
16'-0"	10'-0"	2'-6"	3'-4"	10 #4 @ 18"	2 #4	7 #4 @ 18"	11,000	2,140	#4
16'-0"	12'-0"	3'-0"	3'-4"	12 #4 @ 16"	2 #4	8 #4 @ 18"	13,200	3,070	#4
16'-0"	14'-0"	3'-6"	3'-4"	16 #4 @ 12"	2 #5	9 #4 @ 18"	15,400	4,180	#4
16'-0"	16'-0"	4'-0"	3'-4"	25 #4 @ 7½"	2 #5	11 #4 @ 18"	17,600	5,460	#6
16'-0"	18'-0"	4'-6"	3'-4"	38 #4 @ 5"	3 #5	12 #4 @ 18"	19,800	6,920	#6
16'-0"	20'-0"	5'-0"	3'-4"	32 #5 @ 6"	3 #5	13 #4 @ 18"	20,800	8,500	#6



**BELOW GROUND SILOS  
Panel Placement  
For Both One & Two Tie-Backs**




**SECTION**




**TIE BAR INSERT DETAIL**



**BELOW GROUND SILOS**  
**Panel Placement—Alternate**  
**For Both One & Two Tie-Backs**



Select galvanized strand or cable tie-back and galvanized screw anchor to support the "static tension per tie-back" in Tables 2 and 3.




**INSERT FOR SCREW ANCHOR**



## ABOVE GROUND SILOS Construction


### Construction Steps

1. Grade and uniformly compact dampened sub-grade.
2. Form and cast floor with bars, S, along edges.
3. Excavate for buttress footings 8'-0" on centers.
4. Cast 2" thick, 16" wide, pad for buttresses.
5. Build buttress forms of 2x10 lumber over polyethylene film laid on floor.
6. Place bars, B, (2 per buttress) and cast. Cure before erecting.
7. Place bars, C, and cast 10" thick, 3' wide, footing.
8. Build panel forms of 2x6 lumber along edges of floor slab and over polyethylene film.
9. Place vertical bars, V, on "chairs"; bottom of bar should be 3½" above floor.




Use 3 rows of chairs: 10" from sides of forms and in center


10. Place horizontal bars, H, and corner bars, D, over vertical bars, and wire enough intersections to hold bars in place. Tops of bars should be 1" below tops of forms.
11. Cast and cure panels.
12. Lift panels into place. Wrap bar, D, around loop of bar, B, at top of buttress.
13. Seal joints at floor and buttresses with mortar.




**Step 3.** Excavation for buttress base with key. Buttress footing is 10" thick, plus 6" Key Trench and extends about 8" under floor.



**Step 4.** Concrete Pad 2" thick, 16" wide with key. Do not place concrete in key trench adjacent to pad.




**Step 5.** Buttress forms with reinforcing bars, B, in place.



Place buttress on 2" Concrete Pad plumb and align using wood templates to position buttress. Pad is 16" wide in a 3' wide hole in sod. Cast footing.



# ABOVE GROUND SILOS Buttress




## PLAN AND FOOTING DETAIL

Table 4. Buttress and footing schedule


Dimensions					Reinforcing Bars	
$H_B$	$L_F$	$L_B$	$L_A$	Wt, Lb	B	C
9'-8"	7'-8"	5'-8"	2'-6"	3,400	2 #4 - 24' long	2 #4 - 10'-9" long
11'-8"	8'-8"	6'-8"	3'-0"	4,100	2 #4 - 28' long	2 #4 - 11'-9" long
13'-8"	9'-8"	7'-8"	3'-6"	5,300	2 #6 - 32' long	2 #4 - 12'-9" long
15'-8"	10'-8"	8'-8"	4'-0"	6,000	2 #6 - 36' long	2 #6 - 13'-9" long
17'-8"	11'-8"	9'-8"	4'-6"	6,900	2 #6 - 40' long	2 #6 - 14'-9" long
19'-8"	12'-8"	10'-8"	5'-0"	7,800	2 #8 - 44' long	2 #8 - 15'-9" long




# ABOVE GROUND SILOS Buttress Forms



PLAN  
FORM DETAIL





CUT-AWAY VIEW of footing and buttress, showing position of reinforcing bars



BAR B DETAIL




## ABOVE GROUND SILOS



### INSERT REINFORCING DETAIL

## PANEL FORM



## FORM SECTION

### Table 5. Panel dimension schedule


Panel Height	Width	$I_V$	Weight
10'-0"	7'-11"	3'-0"	5,500
12'-0"	7'-11"	3'-6"	6,600
14'-0"	7'-11"	4'-0"	7,700
16'-0"	7'-11"	4'-6"	8,800
18'-0"	7'-11"	5'-0"	9,900
20'-0"	7'-11"	5'-6"	10,900

**Table 6. Panel reinforcement schedule**


[illegible]




## ABOVE GROUND SILOS Panel Erection



**SILO SECTION**



**TOP OF BUTTRESS** showing panel tie-back rods (Bar D) bent around buttress loops (Bar B)



Courtesy U. of Nebraska

Build an endwall for above ground silos the same as the sidewalls. One method of closing the corner is shown in the photograph:

- The last sidewall panel is cast silage side up instead of silage side down. Reinforcing steel is placed on 1", instead of 3½" chairs.
- A 4"x4" ledge is cast on the silage face of the panel to support the small closing panel in the endwall. Form and cast the ledge at the same time the panel is cast.
- Form and cast a wall panel section, reinforced the same as other panels, to fill the corner.